

# **ADDENDUM # 1**

## **TO THE DRAWINGS AND SPECIFICATIONS FOR: PARKVIEW CREEKBANK STABILIZATION PROJECT**

City of O'Fallon, Missouri  
100 North Main Street  
O'Fallon, Missouri 63366

City of O'Fallon, Missouri 100 North Main Street O'Fallon, MO 63366 636-379-5491 636-978-4144 Fax E-mail: jschuepfer@ofallon.mo.us
---

November 21, 2011

### **INFORMATION**

---

Clarification – the line item “Bedding - MSD Rock Lined Channel Bedding.” Ten inches of MSD rock lined channel bedding are considered incidental to the cost of Rock Lining, and are not paid for under the line item “Bedding-MSD Rock Lined Channel Bedding.” There is one additional instance of this bedding on the plans between stations 2+40 and 2+70 (see cross sections). The line item covers this additional instance of bedding.

Technical Specifications (page TS-20 of 34) Part 6, Section F, Paragraph 8, item C “Installation” – Installation of containerized plants shall be in accordance with ~~industry standard~~ “International Society for Arboriculture’s ANSI A300”. This method shall be followed as a standard for this project.

Station 4+00 to approximately 4+80 as shown on the plans is left undisturbed as far as rock lining goes. The Corps permit has already been issued per the plans and any additional placement of rock would exceed the limitations of the Corps permit. Construction access points through private property are not currently finalized however it will be up to the individual Contractor to define access. The intent is to leave the area between station 4+00 and 4+80 as natural channel. Should the contractor choose to use this area as access, repair plans will be negotiated during the proposed construction access repair plan approval. Any creek bank disturbance shall be restored as nearly as possible to its original condition and covered as detailed in Appendix B Item #1 Construction Access Repair.

**END OF ADDENDUM**